

KANSAS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES

LETTING DATE: June 21, 2023

DATE: 05/19/2023
TIME: 04:00pm

523062131 CONT...

QUANTITY	UNIT	ITEM DESCRIPTION
2,258.50	LNFT	GUARDRAIL, REMOVAL OF STEEL PLATE
3.00	EACH	INLET (TYPE I DITCH)
8.00	EACH	INLET (TYPE II DITCH)
1.00	EACH	INLET (MANHOLE) (SPECIAL)
1.00	EACH	MANHOLE (REINFORCED CONCRETE)
540.00	LNFT	SLOTTED DRAIN (15")
2.30	PMP	MOWING
405.00	SQYD	RIPRAP (LIGHT STONE) (200 LB)
158.00	CUYD	SLOPE PROTECTION (AGGREGATE)
4.00	EACH	GUARDRAIL END TERMINAL (MGS-SRT)
4.00	EACH	GUARDRAIL END TERMINAL (MGS-FLEAT)
4.00	EACH	GUARDRAIL END TERMINAL (MGS-MSKT)
4.00	EACH	GUARDRAIL END TERMINAL (MGS-SOFTSTOP)
4,222.50	LBS.	TEMPORARY FERTILIZER (15-30-15)
559.00	LBS.	TEMPORARY SEED (CANADA WILDRYE)
1,257.80	LBS.	TEMPORARY SEED (GRAIN OATS)
1,257.80	LBS.	TEMPORARY SEED (STERILE WHEATGRASS)
34.00	LBS.	SOIL EROSION MIX
1,017.00	SQYD	EROSION CONTROL (CLASS 1) (TYPE C)
1.00	CUYD	SEDIMENT REMOVAL (SET PRICE)
1.00	LNFT	TEMPORARY BERM (SET PRICE)
12.00	EACH	TEMPORARY INLET SEDIMENT BARRIER
570.00	LNFT	BIODEGRADABLE LOG (20")
570.00	LNFT	FILTER SOCK (18")
1.00	LS	SWPPP DESIGN
119.00	EACH	SWPPP INSPECTION
119.00	EACH	WATER POLLUTION CONTROL MANAGER
12,600.00	LBS.	MULCHING TACKING SLURRY
84.00	TON	MULCHING
1.00	MGAL	WATER (EROSION CONTROL) (SET PRICE)
350.00	CUYD	CLASS I EXCAVATION
359.00	CUYD	CLASS II EXCAVATION
277.00	CUYD	CONCRETE (GRADE 4.0) (AE)
339.60	CUYD	CONCRETE (GRADE 4.0) (AE) (SA)
48,510.00	LBS.	REINFORCING STEEL (GRADE 60)
97,870.00	LBS.	REINFORCING STEEL (GRADE 60) (EPOXY COATED)
1,036.00	LNFT	PILES (STEEL) (HP12X63)
75.00	CUYD	ABUTMENT AGGREGATE DRAIN
91.00	SQYD	BRIDGE BACKWALL PROTECTION SYSTEM
423.00	CUYD	SLOPE PROTECTION (RIPRAP STONE)
1,206.00	LNFT	PRESTRESSED CONCRETE BEAM (K3)
820.00	SQYD	BRIDGE DECK GROOVING
213.00	LNFT	DRILLED SHAFT (42") (CASED)
1.00	EACH	SONIC TEST (DRILLED SHAFT) (SET PRICE)
295.00	LNFT	CORE HOLE (INVESTIGATIVE)
178.10	CUYD	CONCRETE (GRADE 4.0) (RCB BR)
61.10	CUYD	CONCRETE (GRADE 4.0) (AE) (RCB BR)
72.00	SQYD	BRIDGE BACKWALL PROTECTION SYSTEM
15,760.00	LBS.	REINFORCING STEEL (GRADE 60)
19,080.00	LBS.	REINFORCING STEEL (GRADE 60) (EPOXY COATED)

KANSAS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES

LETTING DATE: June 21, 2023

DATE: 05/19/2023
TIME: 04:00pm

523062131 CONT...

QUANTITY	UNIT	ITEM DESCRIPTION
1,450.00	CUYD	CLASS III EXCAVATION (RCB)
34.00	CUYD	FOUNDATION STABILIZATION
574.00	CUYD	GRANULAR BACKFILL (WINGWALLS)
1.00	LS	TEMPORARY SHORING
65,795.00	SQYD	CEMENT TREATED BASE
65,795.00	SQYD	QUALITY CONTROL TESTING (CTB)
65,795.00	SQYD	ASPHALT TREATED BASE
14,311.00	TON	QUALITY CONTROL TESTING (HMA)
1.00	EACH	FIELD OFFICE AND LABORATORY (TYPE A)
1.00	EACH	ASPHALT CORE (SET PRICE)
1.00	EACH	ASPHALT DENSITY PAY ADJUSTMENT
1.00	EACH	ASPHALT AIR VOID PAY ADJUSTMENT
57,666.00	SQYD	CONCRETE PAVEMENT (9" UNIFORM) (AE) (NRDJ)
296.00	SQYD	CONCRETE PAVEMENT (10" UNIFORM) (AE) (BR APP)
35,848.00	SQYD	CONCRETE PAVEMENT (6" UNIFORM) (AE) (PLAIN)
48.00	CUYD	BRIDGE APPROACH SLAB FOOTING
1.00	LS	CONCRETE PAVEMENT SMOOTHNESS
1.00	LS	CONCRETE PAVEMENT COMPOSITE PAY ADJUSTMENT
93,514.00	SQYD	QUALITY CONTROL TESTING (PCCP)
1.00	EACH	CONCRETE CORE (SET PRICE)
824.00	TON	LIME
1.00	MGAL	WATER (LIME TREATED SUBGRADE) (SET PRICE)
66,439.00	SQYD	MANIPULATION (LIME TREATED SUBGRADE)
644.00	SQYD	GRANULAR BASE (4")
35,848.00	SQYD	GRANULAR BASE (7")
1.00	MGAL	WATER (GRANULAR BASE) (SET PRICE)
2,833.00	TON	PAVEMENT EDGE WEDGE (ROCK)
1.00	MGAL	WATER (EARTHWORK COMPACTION) (SET PRICE)
2,477.00	TON	HMA-COMMERCIAL GRADE (CLASS A)
2,158.00	SQYD	AGGREGATE SHOULDER (AS-1) (4")
4,813.00	SQYD	AGGREGATE BASE (AB-3) (6")
1.00	MGAL	WATER (AGGREGATE BASE) (SET PRICE)
1.00	MGAL	WATER (AGGREGATE SHOULDERS) (SET PRICE)
1.00	EACH	FIELD OFFICE AND LABORATORY (TYPE A)
13,292.00	LNFT	FENCE (SINGLE WIRE CABLE)
1.00	EACH	GATE (METAL FARM) (20')
42.00	EACH	POSTS (END) (SINGLE WIRE CABLE)
28.00	EACH	POSTS (PULL) (SINGLE WIRE CABLE)
17.00	EACH	POSTS (CORNER) (SINGLE WIRE CABLE)
419.07	SQFT	SIGN (FLAT SHEET) (HIGH PERFORMANCE)
710.25	SQFT	SIGN (REINFORCED PANEL) (HIGH PERFORMANCE)
830.00	LNFT	SIGN POST (4" X 6" WOOD) (FLAT SHEET SIGN)
401.00	LNFT	SIGN POST (4" X 6" WOOD) (REINFORCED PANEL SIGN)
27.00	LNFT	SIGN POST (3 LB/FT "U" STEEL)
30.00	LNFT	SIGN POST (W 6 X 9 STEEL BEAM)
40.00	LNFT	SIGN POST (W10X12 STEEL BEAM)
2.00	EACH	SIGN POST STUB AND BREAKAWAY BASE PLATE (W 6 X 9)
2.00	EACH	SIGN POST STUB AND BREAKAWAY BASE PLATE (W10X12)
2.00	EACH	SIGN POST BREAKAWAY BASE PLATE (W 6 X 9)
2.00	EACH	SIGN POST BREAKAWAY BASE PLATE (W10X12)

KANSAS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES

LETTING DATE: June 21, 2023

DATE: 05/19/2023
TIME: 04:00pm

523062131 CONT...

QUANTITY	UNIT	ITEM DESCRIPTION
28.00	LNFT	SIGN POST FOOTING (24" STEEL BEAM POST CONCRETE)
207.00	LNFT	SIGN POST FOOTING (18" WOOD POST CONCRETE)
4.00	EACH	SIGNING OBJECT MARKER (TYPE 2)
17.00	EACH	SIGNING DELINEATOR (TYPE A) (WHITE RIGID "U" POST)
5.00	EACH	SIGNING DELINEATOR (TYPE B) (WHITE RIGID "U" POST)
4.00	EACH	SIGNING DELINEATOR (TYPE A) (WHITE FLEXIBLE) (TYPE 1 ANCHOR)
1.00	EACH	SIGNING DELINEATOR (TYPE B) (WHITE FLEXIBLE) (TYPE 1 ANCHOR)
4.00	EACH	SIGNING DELINEATOR (TYPE B) (WHITE FLEXIBLE) (TYPE 3 ANCHOR)
1.00	EACH	OVERHEAD SIGN STRUCTURE (70.1'- 80.0') (STEEL)
36,361.00	LNFT	PAVEMENT MARKING (MULTI-COMPONENT) (WHITE) (6")
28,515.00	LNFT	PAVEMENT MARKING (MULTI-COMPONENT) (YELLOW) (6")
8,680.00	LNFT	PAVEMENT MARKING REMOVAL
1.00	LS	ELECTRIC LIGHTING SYSTEM
1.00	EACH	HIGH MAST LIGHT TOWER (100') (48" CONCRETE BASE)
4,060.00	LBS.	FERTILIZER (13-13-13)
631.20	LBS.	FERTILIZER (15-30-15)
15.80	LBS.	SEED (BIG BLUESTEM GRASS) (KAW)
10.20	LBS.	SEED (BLUE GRAMA GRASS) (LOVINGTON)
91.40	LBS.	SEED (BUFFALO GRASS) (TREATED)
78.90	LBS.	SEED (CANADA WILD-RYE)
15.80	LBS.	SEED (INDIANGRASS) (OSAGE)
15.80	LBS.	SEED (LITTLE BLUESTEM GRASS) (ALDOUS)
913.50	LBS.	SEED (RYEGRASS) (PERENNIAL)
52.80	LBS.	SEED (PRAIRIE JUNE GRASS)
177.60	LBS.	SEED (SIDE OATS GRAMA) (EL RENO)
78.90	LBS.	SEED (STERILE WHEATGRASS)
5.50	LBS.	SEED (SWITCHGRASS) (BLACKWELL)
3.90	LBS.	SEED (TALL DROP)
913.50	LBS.	SEED (FESCUE) (TALL) (ENDOPHYTE-FREE)
153.40	LBS.	SEED (WESTERN WHEATGRASS) (BARTON)
81.30	LBS.	SEED (NATIVE WILDFLOWER MIX 1)
26,220.00	EADA	WORK ZONE SIGNS (0 TO 9.25 SQ.FT.)
37,950.00	EADA	WORK ZONE SIGNS (9.26 TO 16.25 SQ.FT.)
9,660.00	EADA	WORK ZONE SIGNS (16.26 SQ.FT. & OVER)
88,320.00	EADA	WORK ZONE BARRICADES (TYPE 3 - 4 TO 12 LIN. FT.)
166,290.00	EADA	CHANNELIZER (FIXED)
242,880.00	EADA	CHANNELIZER (PORTABLE)
40,020.00	EADA	WORK ZONE WARNING LIGHT (TYPE "A" LOW INTENSITY)
5,520.00	EADA	WORK ZONE WARNING LIGHT (RED TYPE "B" HIGH INTENSITY)
690.00	EADA	ARROW DISPLAY
512.00	STAL	PAVEMENT MARKING (TEMP) 4" SOLID (TYPE I)
573.00	STAL	PAVEMENT MARKING (TEMP) 4" SOLID (TYPE II)
36,851.00	LNFT	PAVEMENT MARKING REMOVAL
481.00	EACH	RIGID RAISED PAVEMENT MARKER (TYPE II)
1.00	LS	TRAFFIC CONTROL (INITIAL SETUP)

*** END OF CONTRACT ***

KANSAS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES

LETTING DATE: June 21, 2023

DATE: 05/19/2023
TIME: 04:00pm

523062141	STATE PROJECT NO: U024-089 KA 3236-01	DBE GOAL: 5.5%
	WORKING DAYS: CCD COMPLETION DATE: 5/28/27	
	COUNTY: SHAWNEE	
	GRADING, BRIDGE AND SURFACING. US-24: BR 084 & BR 085 & BR RPR 086 & BR 087, FR 468 FT E OF THE US24/TOPEKA BLVD INTERS E TO THE SN/JF COLN IN SN CO. LGTH IS 3.66 MI. STATE TIED TO KA 3542-01.	

QUANTITY	UNIT	ITEM DESCRIPTION
1.00	LS	CONTRACTOR CONSTRUCTION STAKING
1.00	EACH	FIELD OFFICE AND LABORATORY (TYPE A)
1.00	CUYD	FOUNDATION STABILIZATION (SET PRICE)
1.00	LS	MOBILIZATION
1.00	LS	MOBILIZATION (DBE)
1.00	LS	REMOVAL OF EXISTING STRUCTURES
6,000.00	HOUR	TRAINEES HIGHWAY CONSTRUCTION (SET PRICE)
1.00	LS	MAINTENANCE AND RESTORATION OF HAUL ROADS (SET PRICE)
1.00	CUYD	CONCRETE FOR SEAL COURSE (SET PRICE)
1.00	LS	CURING ENVIRONMENT
1.00	CUYD	GRANULAR BACKFILL (WINGWALLS) (SET PRICE)
1.00	HOUR	FLAGGER (SET PRICE)
1.00	LS	CLEANING EXISTING STRUCTURE
1.00	LS	TRANSPORTING SALVAGEABLE MATERIAL
1.00	LS	CLEARING AND GRUBBING
162,758.00	SQYD	SALVAGED TOPSOIL
358,590.00	CUYD	COMMON EXCAVATION (URB)
127,240.00	CUYD	ROCK EXCAVATION
42,872.00	CUYD	ROCK EXCAVATION (NON-DURABLE SHALE)
79,302.00	CUYD	COMPACTION OF EARTHWORK (TYPE A) (MR-5-5)
42,425.00	CUYD	COMPACTION OF EARTHWORK (TYPE AA) (MR-0-5)
1.00	MGAL	WATER (GRADING) (SET PRICE)
7,649.00	CUYD	SELECT SOIL (CONTRACTOR FURNISHED)
246.20	CUYD	CONCRETE (GRADE 4.0) (RCB)
6,420.00	LBS.	REINFORCING STEEL (GRADE 60)
22,810.00	LBS.	REINFORCING STEEL (GRADE 60) (EPOXY COATED)
1,488.00	LNFT	CROSS ROAD PIPE (24") (RCP)
132.00	LNFT	CROSS ROAD PIPE (36") (RCP)
330.00	LNFT	CROSS ROAD PIPE (42") (RCP)
20.00	LNFT	CROSS ROAD PIPE (48") (RCP)
74.00	LNFT	CROSS ROAD PIPE (1.5 SQ.FT.) (RCPHE)
262.00	LNFT	CROSS ROAD PIPE (5.0 SQ.FT.) (RCPHE)
150.00	LNFT	CROSS ROAD PIPE (24") (ACSP)
196.00	LNFT	CROSS ROAD PIPE (36") (ACSP)
960.00	LNFT	CROSS ROAD PIPE (15") (CSP)
282.00	LNFT	CROSS ROAD PIPE (18") (CSP)
366.00	LNFT	CROSS ROAD PIPE (30") (CSP)
246.00	LNFT	CROSS ROAD PIPE (30")
156.00	LNFT	CROSS ROAD PIPE (36")
18.00	EACH	END SECTION (24") (RC)
1.00	EACH	END SECTION (30") (RC)
2.00	EACH	END SECTION (42") (RC)
1.00	EACH	END SECTION (48") (RC)
2.00	EACH	END SECTION (1.5 SQ.FT.) (RCHE)
3.00	EACH	END SECTION (3.0 SQ.FT.) (RCHE)

KANSAS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES

LETTING DATE: June 21, 2023

DATE: 05/19/2023
TIME: 04:00pm

523062141 CONT...

QUANTITY	UNIT	ITEM DESCRIPTION
10.00	EACH	END SECTION (5.0 SQ.FT.) (RCHE)
2.00	EACH	END SECTION (7.0 SQ.FT.) (RCHE)
2.00	EACH	END SECTION (24") (CS)
2.00	EACH	END SECTION (36") (CS)
2.00	EACH	END SECTION (6.0 SQ.FT.) (TYPE IV)
2.00	EACH	END SECTION (7.0 SQ.FT.) (TYPE IV)
4.00	EACH	END SECTION (30")
4.00	EACH	END SECTION (36")
82.00	LNFT	ENTRANCE PIPE (3.0 SQ.FT.)
136.00	LNFT	ENTRANCE PIPE (5.0 SQ.FT.)
66.30	CUYD	FLOWABLE FILL (LOW STRENGTH)
4,338.00	LNFT	GUARDRAIL, STEEL PLATE (MGS)
2,291.00	LNFT	GUARDRAIL, STEEL PLATE
7,015.25	LNFT	GUARDRAIL, REMOVAL OF STEEL PLATE
20.00	EACH	INLET (TYPE 22 CURB)
7.00	EACH	INLET (TYPE 22 CURB) (SPECIAL)
10.00	EACH	INLET (TYPE I DITCH)
2.00	EACH	INLET (TYPE II DITCH)
7.00	EACH	INLET (MANHOLE) (SPECIAL)
7.00	EACH	MANHOLE (REINFORCED CONCRETE)
4.00	EACH	PREFABRICATED INTERCEPTION DEVICE (15")
1.00	EACH	PREFABRICATED INTERCEPTION DEVICE (18")
340.00	LNFT	SLOTTED DRAIN (15")
1,093.00	SQYD	CONCRETE DITCH LINING
747.00	TON	AGGREGATE DITCH LINING (4")
234.00	CUYD	SLOPE PROTECTION (AGGREGATE)
320.00	CUYD	SLOPE PROTECTION (RIPRAP STONE)
114.00	LNFT	SLOPE DRAIN (STONE)
2.00	EACH	FLUME INLET (CONCRETE)
978.00	LNFT	STORM SEWER (15") (RCP)
221.00	LNFT	STORM SEWER (18") (RCP)
380.00	LNFT	STORM SEWER (24") (RCP)
97.00	LNFT	STORM SEWER (30") (RCP)
36.00	LNFT	STORM SEWER (1.5 SQ.FT.) (RCPHE)
156.00	LNFT	STORM SEWER (3.0 SQ.FT.) (RCPHE)
873.00	LNFT	STORM SEWER (5.0 SQ.FT.) (RCPHE)
71.00	LNFT	STORM SEWER (6.0 SQ.FT.) (RCPHE)
610.00	LNFT	STORM SEWER (7.0 SQ.FT.) (RCPHE)
130.00	SQYD	SIDEWALK CONSTRUCTION (4") (AE)
16.00	SQYD	SIDEWALK RAMP
3.70	PMPS	MOWING
7.00	EACH	RIGHT-OF-WAY SURVEY MONUMENT
87.00	CUYD	FOUNDATION STABILIZATION
48.00	CUYD	GRANULAR BACKFILL (WINGWALLS)
349.00	SQYD	BRIDGE BACKWALL PROTECTION SYSTEM
1.00	LS	TEMPORARY SHORING
696.00	LNFT	LINER PIPE (84")
696.00	LNFT	LINER PIPE (96")
7.00	EACH	GUARDRAIL END TERMINAL (MGS-SRT)
7.00	EACH	GUARDRAIL END TERMINAL (MGS-FLEAT)

KANSAS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES

LETTING DATE: June 21, 2023

DATE: 05/19/2023
TIME: 04:00pm

523062141 CONT...

QUANTITY	UNIT	ITEM DESCRIPTION
10.00	EACH	GUARDRAIL END TERMINAL (MGS-MSKT)
10.00	EACH	GUARDRAIL END TERMINAL (MGS-SOFTSTOP)
12,320.60	LBS.	TEMPORARY FERTILIZER (15-30-15)
573.00	LBS.	TEMPORARY SEED (RYEGRASS-ANNUAL)
1,407.50	LBS.	TEMPORARY SEED (CANADA WILDRYE)
3,167.00	LBS.	TEMPORARY SEED (GRAIN OATS)
3,167.00	LBS.	TEMPORARY SEED (STERILE WHEATGRASS)
33.00	LBS.	SOIL EROSION MIX
1,343.00	SQYD	EROSION CONTROL (CLASS 1) (TYPE C)
1.00	CUYD	SEDIMENT REMOVAL (SET PRICE)
1.00	LNFT	TEMPORARY BERM (SET PRICE)
440.00	CUYD	TEMPORARY DITCH CHECK (ROCK)
26.00	EACH	TEMPORARY INLET SEDIMENT BARRIER
1,609.50	LNFT	BIODEGRADABLE LOG (9")
2,146.00	LNFT	BIODEGRADABLE LOG (12")
1,630.00	LNFT	BIODEGRADABLE LOG (20")
1,609.50	LNFT	FILTER SOCK (12")
1,475.00	LNFT	FILTER SOCK (18")
465.00	LNFT	SILT FENCE
1.00	LS	SWPPP DESIGN
200.00	EACH	SWPPP INSPECTION
200.00	EACH	WATER POLLUTION CONTROL MANAGER
36,900.00	LBS.	MULCHING TACKING SLURRY
254.40	TON	MULCHING
1.00	MGAL	WATER (EROSION CONTROL) (SET PRICE)
320.00	CUYD	CLASS I EXCAVATION
49.00	CUYD	CLASS II EXCAVATION
210.20	CUYD	CONCRETE (GRADE 4.0) (AE)
435.50	CUYD	CONCRETE (GRADE 4.0) (AE) (SA)
35,300.00	LBS.	REINFORCING STEEL (GRADE 60)
148,270.00	LBS.	REINFORCING STEEL (GRADE 60) (EPOXY COATED)
890.00	LNFT	PILES (STEEL) (HP12X74)
79.00	LNFT	TEST PILES (SPECIAL) (HP12X74)
14.00	EACH	CAST STEEL PILE POINTS
297.00	LNFT	DRILLED SHAFT (48") (CASED)
1.00	EACH	SONIC TEST (DRILLED SHAFT) (SET PRICE)
88.00	SQYD	BRIDGE BACKWALL PROTECTION SYSTEM
126.00	CUYD	ABUTMENT AGGREGATE DRAIN
766.00	CUYD	SLOPE PROTECTION (RIPRAP STONE)
1,260.00	LNFT	PRESTRESSED CONCRETE BEAM (NU43+1)
1,024.00	SQYD	BRIDGE DECK GROOVING
167.00	LNFT	CORE HOLE (INVESTIGATIVE)
320.00	CUYD	CLASS I EXCAVATION
49.00	CUYD	CLASS II EXCAVATION
210.20	CUYD	CONCRETE (GRADE 4.0) (AE)
435.50	CUYD	CONCRETE (GRADE 4.0) (AE) (SA)
35,300.00	LBS.	REINFORCING STEEL (GRADE 60)
148,270.00	LBS.	REINFORCING STEEL (GRADE 60) (EPOXY COATED)
890.00	LNFT	PILES (STEEL) (HP12X74)
79.00	LNFT	TEST PILES (SPECIAL) (HP12X74)

KANSAS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES

LETTING DATE: June 21, 2023

DATE: 05/19/2023
TIME: 04:00pm

523062141 CONT...

QUANTITY	UNIT	ITEM DESCRIPTION
14.00	EACH	CAST STEEL PILE POINTS
297.00	LNFT	DRILLED SHAFT (48") (CASED)
1.00	EACH	SONIC TEST (DRILLED SHAFT) (SET PRICE)
88.00	SQYD	BRIDGE BACKWALL PROTECTION SYSTEM
126.00	CUYD	ABUTMENT AGGREGATE DRAIN
766.00	CUYD	SLOPE PROTECTION (RIPRAP STONE)
1,260.00	LNFT	PRESTRESSED CONCRETE BEAM (NU43+1)
1,024.00	SQYD	BRIDGE DECK GROOVING
167.00	LNFT	CORE HOLE (INVESTIGATIVE)
545.00	SQYD	MULTI-LAYER POLYMER CONCRETE OVERLAY
10.00	SQYD	AREA PREPARED FOR PATCHING
5.00	SQYD	AREA PREPARED FOR PATCHING (FULL DEPTH)
57.80	CUYD	CONCRETE (GRADE 4.0) (AE) (SA)
18,600.00	LBS.	REINFORCING STEEL (GRADE 60) (EPOXY COATED)
10.00	SQFT	CONCRETE SURFACE REPAIR
70.00	CUYD	SLOPE PROTECTION (RIPRAP STONE)
232.00	CUYD	SLOPE PROTECTION (AGGREGATE)
4.00	EACH	DRILLING AND GROUTING
1.00	LBS.	REINFORCING STEEL (REPAIR) (GRADE 60) (EPOXY) (SET PRICE)
248.00	EACH	EMBEDDED GALVANIC ANODE
545.00	SQYD	MULTI-LAYER POLYMER CONCRETE OVERLAY
10.00	SQYD	AREA PREPARED FOR PATCHING
5.00	SQYD	AREA PREPARED FOR PATCHING (FULL DEPTH)
57.80	CUYD	CONCRETE (GRADE 4.0) (AE) (SA)
18,600.00	LBS.	REINFORCING STEEL (GRADE 60) (EPOXY COATED)
10.00	SQFT	CONCRETE SURFACE REPAIR
70.00	CUYD	SLOPE PROTECTION (RIPRAP STONE)
4.00	EACH	DRILLING AND GROUTING
1.00	LBS.	REINFORCING STEEL (REPAIR) (GRADE 60) (EPOXY) (SET PRICE)
250.00	EACH	EMBEDDED GALVANIC ANODE
137,376.00	SQYD	CEMENT TREATED BASE
137,376.00	SQYD	QUALITY CONTROL TESTING (CTB)
137,376.00	SQYD	ASPHALT TREATED BASE
29,880.00	TON	QUALITY CONTROL TESTING (HMA)
1.00	EACH	ASPHALT AIR VOID PAY ADJUSTMENT
1.00	EACH	ASPHALT DENSITY PAY ADJUSTMENT
1.00	EACH	ASPHALT CORE (SET PRICE)
1.00	EACH	FIELD OFFICE AND LABORATORY (TYPE A)
2,607.00	LNFT	CURB AND GUTTER, COMBINED (AE)
12,441.00	LNFT	CURB AND GUTTER, COMBINED (AE) (SPECIAL)
1,363.00	SQYD	CONCRETE PAVEMENT (6" UNIFORM) (AE) (NRDJ)
1,122.00	SQYD	CONCRETE PAVEMENT (7" UNIFORM) (AE) (NRDJ)
30,217.00	SQYD	CONCRETE PAVEMENT (8" UNIFORM) (AE) (NRDJ)
460.00	SQYD	CONCRETE PAVEMENT (8.5" UNIFORM) (AE) (NRDJ)
117,516.00	SQYD	CONCRETE PAVEMENT (9" UNIFORM) (AE) (NRDJ)
2,337.00	SQYD	CONCRETE PAVEMENT (10" UNIFORM) (AE) (BR APP)
62,706.00	SQYD	CONCRETE PAVEMENT (6" UNIFORM) (AE) (PLAIN)
320.30	CUYD	BRIDGE APPROACH SLAB FOOTING
1.00	EACH	CONCRETE PAVEMENT SMOOTHNESS
1.00	EACH	CONCRETE PAVEMENT COMPOSITE PAY ADJUSTMENT

KANSAS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES

LETTING DATE: June 21, 2023

DATE: 05/19/2023
TIME: 04:00pm

523062141 CONT...

QUANTITY	UNIT	ITEM DESCRIPTION
213,384.00	SQYD	QUALITY CONTROL TESTING (PCCP)
1.00	EACH	CONCRETE CORE (SET PRICE)
2,128.00	TON	LIME
1.00	MGAL	WATER (LIME TREATED SUBGRADE) (SET PRICE)
171,618.00	SQYD	MANIPULATION (LIME TREATED SUBGRADE)
34,242.00	SQYD	GRANULAR BASE (4")
54,176.00	SQYD	GRANULAR BASE (7")
1.00	MGAL	WATER (GRANULAR BASE) (SET PRICE)
4,847.00	TON	PAVEMENT EDGE WEDGE (ROCK)
1.00	MGAL	WATER (EARTHWORK COMPACTION) (SET PRICE)
6,054.00	TON	HMA-COMMERCIAL GRADE (CLASS A)
73.00	TON	SURFACING MATERIAL (AB-3)
12,872.00	SQYD	AGGREGATE BASE (AB-3) (6")
3,542.00	SQYD	AGGREGATE SHOULDER (AS-1) (4")
1.00	MGAL	WATER (AGGREGATE BASE) (SET PRICE)
1.00	MGAL	WATER (AGGREGATE SHOULDERS) (SET PRICE)
1.00	EACH	FIELD OFFICE AND LABORATORY (TYPE A)
2,558.00	LNFT	FENCE (SINGLE WIRE CABLE)
2.00	EACH	GATE (CHAIN LINK FENCE) (14')
6.00	EACH	POSTS (END) (SINGLE WIRE CABLE)
14.00	EACH	POSTS (CORNER) (SINGLE WIRE CABLE)
1,427.48	SQFT	SIGN (FLAT SHEET) (HIGH PERFORMANCE)
1,583.50	SQFT	SIGN (REINFORCED PANEL) (HIGH PERFORMANCE)
2,764.00	LNFT	SIGN POST (4" X 6" WOOD) (FLAT SHEET SIGN)
511.00	LNFT	SIGN POST (4" X 6" WOOD) (REINFORCED PANEL SIGN)
108.00	LNFT	SIGN POST (3 LB/FT "U" STEEL)
136.00	LNFT	SIGN POST (W 6 X 9 STEEL BEAM)
202.00	LNFT	SIGN POST (W10X12 STEEL BEAM)
8.00	EACH	SIGN POST STUB AND BREAKAWAY BASE PLATE (W 6 X 9)
10.00	EACH	SIGN POST STUB AND BREAKAWAY BASE PLATE (W10X12)
8.00	EACH	SIGN POST BREAKAWAY BASE PLATE (W 6 X 9)
10.00	EACH	SIGN POST BREAKAWAY BASE PLATE (W10X12)
128.00	LNFT	SIGN POST FOOTING (24" STEEL BEAM POST CONCRETE)
240.00	LNFT	SIGN POST FOOTING (18" WOOD POST CONCRETE)
12.00	EACH	SIGNING OBJECT MARKER (TYPE 2)
37.00	EACH	SIGNING DELINEATOR (TYPE A) (WHITE RIGID "U" POST)
33.00	EACH	SIGNING DELINEATOR (TYPE B) (WHITE RIGID "U" POST)
4.00	EACH	SIGNING DELINEATOR (TYPE B) (YELLOW RIGID "U" POST)
5.00	EACH	SIGNING DELINEATOR (TYPE A) (WHITE FLEXIBLE) (TYPE 1 ANCHOR)
24.00	EACH	SIGNING DELINEATOR (TYPE B) (WHITE FLEXIBLE) (TYPE 1 ANCHOR)
1.00	EACH	CANTILEVER SIGN STRUCTURE (25.1'-30.0') (STEEL)
1.00	EACH	CANTILEVER SIGN STRUCTURE (30.1'-35.0') (STEEL)
21,246.00	LNFT	PAVEMENT MARKING (MULTI-COMPONENT) (WHITE) (4")
65,576.00	LNFT	PAVEMENT MARKING (MULTI-COMPONENT) (WHITE) (6")
4,456.00	LNFT	PAVEMENT MARKING (MULTI-COMPONENT) (WHITE) (8")
1,338.00	LNFT	PAVEMENT MARKING (MULTI-COMPONENT) (WHITE) (12")
24,124.00	LNFT	PAVEMENT MARKING (MULTI-COMPONENT) (YELLOW) (4")
48,227.00	LNFT	PAVEMENT MARKING (MULTI-COMPONENT) (YELLOW) (6")
81.00	LNFT	PAVEMENT MARKING (MULTI-COMPONENT) (YELLOW) (12")
906.00	LNFT	PAVEMENT MARKING (INTERSECTION GRADE) (WHITE) (24")

KANSAS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES

LETTING DATE: June 21, 2023

DATE: 05/19/2023
TIME: 04:00pm

523062141 CONT...

QUANTITY	UNIT	ITEM DESCRIPTION
1.00	EACH	PAVEMENT MRK SYM (INTERSECTION GRADE) (WHITE) THRU-RT ARROW
5.00	EACH	PAVEMENT MRK SYM (INTERSECTION GRADE) (WHITE) (LT & RT)
13.00	EACH	PAVEMENT MRK SYM (INTERSECTION GRADE) (WHITE) (RT ARROW)
30.00	EACH	PAVEMENT MRK SYM (INTERSECTION GRADE) (WHITE) (LEFT ARROW)
25,998.00	LNFT	PAVEMENT MARKING REMOVAL
1.00	LS	ELECTRIC LIGHTING SYSTEM
3.00	EACH	HIGH MAST LIGHT TOWER (100') (48" CONCRETE BASE)
1.00	LS	TRAFFIC SIGNAL
1.00	LS	RADAR DETECTION SYSTEM
1.00	LS	TRANSPORTING SALVAGEABLE MATERIAL
3,720.00	LBS.	FERTILIZER (13-13-13)
5,056.00	LBS.	FERTILIZER (15-30-15)
126.40	LBS.	SEED (BIG BLUESTEM GRASS) (KAW)
9.30	LBS.	SEED (BLUE GRAMA GRASS) (LOVINGTON)
83.70	LBS.	SEED (BUFFALO GRASS) (TREATED)
632.00	LBS.	SEED (CANADA WILD-RYE)
126.40	LBS.	SEED (INDIANGRASS) (OSAGE)
126.40	LBS.	SEED (LITTLE BLUESTEM GRASS) (ALDOUS)
837.00	LBS.	SEED (RYEGRASS) (PERENNIAL)
48.40	LBS.	SEED (PRAIRIE JUNE GRASS)
515.30	LBS.	SEED (SIDE OATS GRAMA) (EL RENO)
632.00	LBS.	SEED (STERILE WHEATGRASS)
44.20	LBS.	SEED (SWITCHGRASS) (BLACKWELL)
31.60	LBS.	SEED (TALL DROP)
837.00	LBS.	SEED (FESCUE) (TALL) (ENDOPHYTE-FREE)
364.40	LBS.	SEED (WESTERN WHEATGRASS) (BARTON)
651.00	LBS.	SEED (NATIVE WILDFLOWER MIX 1)
695,250.00	EADA	WORK ZONE SIGNS (0 TO 9.25 SQ.FT.)
120,380.00	EADA	WORK ZONE SIGNS (9.26 TO 16.25 SQ.FT.)
27,000.00	EADA	WORK ZONE SIGNS (16.26 SQ.FT. & OVER)
128,250.00	EADA	WORK ZONE BARRICADES (TYPE 3 - 4 TO 12 LIN. FT.)
2,250.00	EADA	WORK ZONE BARRICADES (PEDESTRIAN)
290,250.00	EADA	CHANNELIZER (FIXED)
492,750.00	EADA	CHANNELIZER (PORTABLE)
103,500.00	EADA	WORK ZONE WARNING LIGHT (TYPE "A" LOW INTENSITY)
9,000.00	EADA	WORK ZONE WARNING LIGHT (RED TYPE "B" HIGH INTENSITY)
5,630.00	EADA	ARROW DISPLAY
2,250.00	EADA	PORTABLE CHANGEABLE MESSAGE SIGN
1,447.00	STAL	PAVEMENT MARKING (TEMP) 4" SOLID (TYPE I)
1,274.00	STAL	PAVEMENT MARKING (TEMP) 4" SOLID (TYPE II)
79,892.00	LNFT	PAVEMENT MARKING REMOVAL
4.00	EACH	IMPACT ATTENUATOR (TL-3) (TEMPORARY)
10.00	EACH	REPLACEMENT MODULES (IMPACT ATTENUATOR)
42.00	EACH	WORK ZONE SIGN (SPECIAL) (16.26 SQ.FT. & OVER)
516.00	EACH	RIGID RAISED PAVEMENT MARKER (TYPE II)
1.00	LS	TRAFFIC CONTROL (INITIAL SETUP)
4,175.00	LNFT	CONCRETE SAFETY BARRIER (TYPE F3) (TEMPORARY)
3,850.00	LNFT	CONCRETE SAFETY BARRIER (TYPE F3) (TEMPORARY - RELOCATE)

*** END OF CONTRACT ***

KANSAS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES

LETTING DATE: June 21, 2023

DATE: 05/19/2023
TIME: 04:00pm

523062363	STATE PROJECT NO: I070-091 KA 6777-01	DBE GOAL:	0.0%
	WORKING DAYS: CCD COMPLETION DATE: 11/15/24		
	COUNTY: SHERMAN		
	BRIDGE REPAIR. I-70; BR NO (027) AND (028) 2 MI E OF K-27 IN SH. CO. LGTH 0.02 MI.		

QUANTITY	UNIT	ITEM DESCRIPTION
1.00	LS	CONTRACTOR CONSTRUCTION STAKING
1.00	LS	MOBILIZATION
1.00	LS	MOBILIZATION (DBE)
1.00	LS	REMOVAL OF EXISTING STRUCTURES
1.00	HOUR	FLAGGER (SET PRICE)
123.00	CUYD	COMMON EXCAVATION (RURAL SMALL)
40.00	CUYD	COMPACTION OF EARTHWORK (TYPE B) (MR-90)
1.00	MGAL	WATER (GRADING) (SET PRICE)
800.00	LNFT	GUARDRAIL, STEEL PLATE (MGS)
1.00	EACH	TOWING (COURTESY) (SET PRICE)
4.00	EACH	GUARDRAIL END TERMINAL (MGS-SRT)
4.00	EACH	GUARDRAIL END TERMINAL (MGS-FLEAT)
74.00	LBS.	TEMPORARY FERTILIZER (16-20- 0)
83.30	LBS.	SOIL EROSION MIX
2,358.00	SQYD	EROSION CONTROL (CLASS 1) (TYPE C)
800.00	LNFT	BIODEGRADABLE LOG (20")
800.00	LNFT	FILTER SOCK (18")
500.00	SQYD	GEOTEXTILE (EROSION CONTROL)
1.00	MGAL	WATER (EROSION CONTROL) (SET PRICE)
29.00	CUYD	CONCRETE (GRADE 4.0) (AE) (SW)
5,780.00	LBS.	REINFORCING STEEL (GRADE 60) (EPOXY COATED)
160.00	EACH	DRILLING AND GROUTING
760.00	SQYD	MACHINE PREPARATION (1.75")
50.00	SQYD	AREA PREPARED FOR PATCHING
5.00	SQYD	AREA PREPARED FOR PATCHING (FULL DEPTH)
760.00	SQYD	PORTLAND CEMENT CONCRETE OVERLAY (1.75")
1.00	LBS.	REINFORCING STEEL (REPAIR) (GRADE 60) (EPOXY) (SET PRICE)
1.00	CUYD	MATERIAL FOR PORTLAND CEMENT CONCRETE OVERLAY (SET PRICE)
684.00	SQYD	BRIDGE DECK GROOVING
50.00	SQFT	CONCRETE SURFACE REPAIR
29.00	CUYD	CONCRETE (GRADE 4.0) (AE) (SW)
5,780.00	LBS.	REINFORCING STEEL (GRADE 60) (EPOXY COATED)
160.00	EACH	DRILLING AND GROUTING
760.00	SQYD	MACHINE PREPARATION (1.75")
70.00	SQYD	AREA PREPARED FOR PATCHING
5.00	SQYD	AREA PREPARED FOR PATCHING (FULL DEPTH)
760.00	SQYD	PORTLAND CEMENT CONCRETE OVERLAY (1.75")
1.00	LBS.	REINFORCING STEEL (REPAIR) (GRADE 60) (EPOXY) (SET PRICE)
1.00	CUYD	MATERIAL FOR PORTLAND CEMENT CONCRETE OVERLAY (SET PRICE)
684.00	SQYD	BRIDGE DECK GROOVING
200.00	SQFT	CONCRETE SURFACE REPAIR
6.00	TON	HMA-COMMERCIAL GRADE (CLASS A)
1,950.00	EADA	WORK ZONE SIGNS (0 TO 9.25 SQ.FT.)
5,460.00	EADA	WORK ZONE SIGNS (9.26 TO 16.25 SQ.FT.)
1,950.00	EADA	WORK ZONE SIGNS (16.26 SQ.FT. & OVER)
1,170.00	EADA	WORK ZONE BARRICADES (TYPE 3 - 4 TO 12 LIN. FT.)

KANSAS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES

LETTING DATE: June 21, 2023

DATE: 05/19/2023
TIME: 04:00pm

523062363 CONT...

QUANTITY	UNIT	ITEM DESCRIPTION
19,500.00	EADA	CHANNELIZER (PORTABLE)
1,560.00	EADA	WORK ZONE WARNING LIGHT (TYPE "A" LOW INTENSITY)
390.00	EADA	ARROW DISPLAY
98.00	STAL	PAVEMENT MARKING (TEMP) 4" SOLID (TYPE I)
5,090.00	LNFT	PAVEMENT MARKING REMOVAL
1.00	LS	TRAFFIC CONTROL (INITIAL SETUP)
1,375.00	LNFT	CONCRETE SAFETY BARRIER (TYPE F3) (TEMPORARY)
1,375.00	LNFT	CONCRETE SAFETY BARRIER (TYPE F3) (TEMPORARY - RELOCATE)
2.00	EACH	INERTIAL BARRIER SYSTEM (TL-3)
15.00	EACH	REPLACEMENT MODULES (IBS)
*** END OF CONTRACT ***		

SUMMARY OF QUANTITIES

DATE: 05/19/2023

LETTING DATE: June 21, 2023

TIME: 04:00pm

523062434

STATE PROJECT NO: 011 C 5135-01

DBE GOAL:

0.0%

WORKING DAYS: 100 COMPLETION DATE:

COUNTY: CHEROKEE

SIGNING. MAJOR COLLECTORS E OF K-7, IN CK CO. LGTH 93.44 MI.

QUANTITY	UNIT	ITEM DESCRIPTION
1.00	LS	MOBILIZATION
1.00	LS	MOBILIZATION (DBE)
1.00	LS	CONTRACTOR CONSTRUCTION STAKING
1.00	LS	REMOVAL OF EXISTING STRUCTURES
1.00	HOUR	FLAGGER (SET PRICE)
1.00	LS	TRAFFIC CONTROL
2,949.83	SQFT	SIGN (FLAT SHEET) (HIGH PERFORMANCE)
5,938.00	LNFT	SIGN POST (1-3/4" PERFORATED SQUARE STEEL TUBE)
502.00	EACH	SIGN POST FOOTING (1-3/4" PERFORATED SQUARE STEEL TUBE)
82.00	EACH	SIGNING OBJECT MARKER (TYPE 2)
96.00	EACH	SIGNING OBJECT MARKER (TYPE 3)
364.00	EACH	SIGNING OBJECT MARKER (TYPE 2) (DOUBLE)
80.00	EACH	SIGNING OBJECT MARKER (TYPE 3) (DOUBLE)
1.00	LS	SIGN (REMOVE AND RESET)

*** END OF CONTRACT ***

SUMMARY OF QUANTITIES

DATE: 05/19/2023

LETTING DATE: June 21, 2023

TIME: 04:00pm

523062595 STATE PROJECT NO: K254-008 KA 6981-01 DBE GOAL: 0.0%
 WORKING DAYS: 50 COMPLETION DATE:
 COUNTY: BUTLER
 PAVEMENT MARKING. K-254; FR SG/BU CO LI TO WCL OF EL DORADO IN BU CO.
 LGTH 14.0 MI.

QUANTITY	UNIT	ITEM DESCRIPTION
1.00	LS	MOBILIZATION
1.00	LS	MOBILIZATION (DBE)
1.00	LS	TRAFFIC CONTROL
1.00	HOUR	FLAGGER (SET PRICE)
209,389.00	LNFT	PAVEMENT MARKING (MULTI-COMPONENT) (WHITE) (6")
1,294.00	LNFT	PAVEMENT MARKING (MULTI-COMPONENT) (YELLOW) (4")
151,440.00	LNFT	PAVEMENT MARKING (MULTI-COMPONENT) (YELLOW) (6")
415.00	LNFT	PAVEMENT MARKING (INTERSECTION GRADE) (WHITE) (24")
135.00	EACH	PAVEMENT MRK SYM (INTERSECTION GRADE) (WHITE) (LEFT ARROW)
47.00	EACH	PAVEMENT MRK SYM (INTERSECTION GRADE) (WHITE) (RT ARROW)
362,123.00	LNFT	PAVEMENT MARKING REMOVAL

*** END OF CONTRACT ***

SUMMARY OF QUANTITIES

DATE: 05/19/2023

LETTING DATE: June 21, 2023

TIME: 04:00pm

523062616

STATE PROJECT NO: U083-106 KA 6234-01

DBE GOAL:

0.0%

WORKING DAYS: 315 COMPLETION DATE:

COUNTY: STATEWIDE

INTELLIGENT TRANSPORTATION SYSTEM. US-83 APPROX FROM THE U.S. 83 / U.S. 50 / U.S. 400 JUNCTN IN GARDEN CITY N TO I-70/U.S. 83 JUNCTN IN TH CO.

QUANTITY	UNIT	ITEM DESCRIPTION
1.00	LS	CONTRACTOR CONSTRUCTION STAKING
1.00	LS	MOBILIZATION
1.00	LS	MOBILIZATION (DBE)
1.00	LS	TRAFFIC CONTROL
1.00	HOUR	FLAGGER (SET PRICE)
10.00	CUYD	COMPACTION OF EARTHWORK (TYPE B) (MR-0-5)
10.00	CUYD	GRANULAR BACKFILL
1.00	MGAL	WATER (GRADING) (SET PRICE)
48.00	SQYD	CONCRETE PAVEMENT (12" UNIFORM) (AE) (PLAIN)
11.00	TON	HMA-COMMERCIAL GRADE (CLASS A)
176.00	LNFT	FENCE (CHAIN LINK) (8'-0")
1.00	LS	INTELLIGENT TRANSPORTATION SYSTEM
		*** END OF CONTRACT ***

SUMMARY OF QUANTITIES

DATE: 05/19/2023
 TIME: 04:00pm

LETTING DATE: June 21, 2023

523064232 STATE PROJECT NO: 057 C 5127-01 DBE GOAL: 1.0%
 WORKING DAYS: 20 COMPLETION DATE:
 COUNTY: MARION
 GRADING AND SURFACING. INDIGO RD NEAR 130TH RD IN MN CO. LGTH IS 0.101
 MI.

QUANTITY	UNIT	ITEM DESCRIPTION
1.00	LS	CONTRACTOR CONSTRUCTION STAKING
1.00	EACH	FIELD OFFICE AND LABORATORY (TYPE A)
1.00	LS	MOBILIZATION
1.00	LS	MOBILIZATION (DBE)
1.00	LS	TRAFFIC CONTROL
1.00	HOUR	FLAGGER (SET PRICE)
1.00	LS	CLEARING AND GRUBBING
202.00	CUYD	COMMON EXCAVATION (RURAL SMALL)
37.00	CUYD	COMPACTION OF EARTHWORK (TYPE B) (MR-90)
1.00	MGAL	WATER (GRADING) (SET PRICE)
1.00	CUYD	TEMPORARY SURFACING MATERIAL (AGGREGATE) (SET PRICE)
1.00	EACH	MAILBOX INSTALLATION (SET PRICE)
1.00	CUYD	SEDIMENT REMOVAL (SET PRICE)
1.00	LNFT	TEMPORARY BERM (SET PRICE)
35.00	LNFT	BIODEGRADABLE LOG (9")
35.00	LNFT	BIODEGRADABLE LOG (12")
39.00	LNFT	BIODEGRADABLE LOG (20")
1.00	MGAL	WATER (EROSION CONTROL) (SET PRICE)
292.00	TON	HMA-COMMERCIAL GRADE (CLASS A)
658.00	SQYD	AGGREGATE BASE (AB-3) (6")
1.00	MGAL	WATER (AGGREGATE BASE) (SET PRICE)
1.00	LS	SIGN (REMOVE AND RESET)
1.00	LS	SEEDING

*** END OF CONTRACT ***

SUMMARY OF QUANTITIES

DATE: 05/19/2023
 TIME: 04:00pm

LETTING DATE: June 21, 2023

523066161

STATE PROJECT NO: I035-046 KA 6074-02 DBE GOAL:
 WORKING DAYS: 55 COMPLETION DATE:
 COUNTY: JOHNSON
 GUARDRAIL. I-35: FR 2.6 MI S OF 151ST ST N TO 151ST ST IN JO CO. LGTH IS 2.352 MI.

QUANTITY	UNIT	ITEM DESCRIPTION
1.00	LS	CONTRACTOR CONSTRUCTION STAKING
1.00	LS	MOBILIZATION
1.00	LS	TRAFFIC CONTROL
1.00	HOUR	FLAGGER (SET PRICE)
1.00	LS	CLEARING AND GRUBBING
258.00	CUYD	COMMON EXCAVATION (RURAL SMALL)
17.00	CUYD	COMMON EXCAVATION (CONTRACTOR FURNISHED)
129.00	CUYD	COMPACTION OF EARTHWORK (TYPE A) (MR-5-5)
1.00	MGAL	WATER (GRADING) (SET PRICE)
2,812.50	LNFT	GUARDRAIL, STEEL PLATE (MGS)
3,094.00	LNFT	GUARDRAIL, REMOVAL OF STEEL PLATE
1.00	MGAL	WATER (EARTHWORK COMPACTION) (SET PRICE)
673.00	TON	PAVEMENT EDGE WEDGE (ROCK)
3,302.00	SQYD	SEPARATION GEOTEXTILE
12.00	EACH	GUARDRAIL END TERMINAL (MGS-FLEAT)
12.00	EACH	GUARDRAIL END TERMINAL (MGS-SRT)
2.00	EACH	GUARDRAIL END TERMINAL (MGS-MSKT)
2.00	EACH	GUARDRAIL END TERMINAL (MGS-SOFTSTOP)
1.00	CUYD	SEDIMENT REMOVAL (SET PRICE)
1.00	LNFT	TEMPORARY BERM (SET PRICE)
1.00	MGAL	WATER (EROSION CONTROL) (SET PRICE)
5.00	EACH	SIGNING OBJECT MARKER (TYPE 2)
1.00	LS	SEEDING

*** END OF CONTRACT ***

KANSAS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES

LETTING DATE: June 21, 2023

DATE: 05/19/2023
TIME: 04:00pm

523066262 STATE PROJECT NO: K014-053 KA 6854-01 DBE GOAL:
WORKING DAYS: 55 COMPLETION DATE:
COUNTY: LINCOLN
SIDEWALK IMPROVEMENTS. CITY OF LINCOLN IN LC CO.

QUANTITY	UNIT	ITEM DESCRIPTION
1.00	LS	CONTRACTOR CONSTRUCTION STAKING
1.00	LS	MOBILIZATION
1.00	LS	TRAFFIC CONTROL
1.00	HOURL	FLAGGER (SET PRICE)
1.00	LS	CLEARING AND GRUBBING
24.00	CUYD	COMMON EXCAVATION (URB)
18.00	CUYD	ROCK EXCAVATION
134.00	SQYD	SIDEWALK CONSTRUCTION (4") (AE)
116.00	SQYD	SIDEWALK RAMP
174.00	SQFT	TEMPORARY PEDESTRIAN SURFACE
3.60	CUYD	CONCRETE (GRADE 3.0) (AE)
120.00	LBS.	REINFORCING STEEL (GRADE 60)
10.00	STAL	PAVEMENT MARKING (TEMP) 4" SOLID (TYPE I)
2.00	STAL	PAVEMENT MARKING (TEMP) (SOLID) (LINE MASKING TAPE)
1.00	CUYD	SEDIMENT REMOVAL (SET PRICE)
1.00	LNFT	TEMPORARY BERM (SET PRICE)
40.00	LNFT	FILTER SOCK (8")
1.00	MGAL	WATER (EROSION CONTROL) (SET PRICE)
336.00	LNFT	CURB AND GUTTER, COMBINED (AE)
1.00	LS	SIGN (REMOVE AND RESET)
63.00	LNFT	SIGN POST (4" X 6" WOOD) (FLAT SHEET SIGN)
1.00	LS	SEEDING

*** END OF CONTRACT ***

KANSAS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES

LETTING DATE: June 21, 2023

DATE: 05/19/2023
TIME: 04:00pm

523066282 STATE PROJECT NO: U036-101 KA 6779-01 DBE GOAL:
 WORKING DAYS: 90 COMPLETION DATE:
 COUNTY: WASHINGTON
 BRIDGE REPAIR US-36; BR NO 36-101-269.15(043) OVER CAMP CREEK AND BR NO
 36-101-270.12(045) OVER MILL CREEK IN WS CO. LGTH 0.002.

QUANTITY	UNIT	ITEM DESCRIPTION
1.00	LS	MOBILIZATION
1.00	HOUR	FLAGGER (SET PRICE)
1.00	LS	CONTRACTOR CONSTRUCTION STAKING
18.00	CUYD	ROCK EXCAVATION
87.00	CUYD	COMMON EXCAVATION (RURAL SMALL)
648.00	SQYD	MACHINE PREPARATION (1.50")
50.00	SQYD	AREA PREPARED FOR PATCHING
5.00	SQYD	AREA PREPARED FOR PATCHING (FULL DEPTH)
648.00	SQYD	PORTLAND CEMENT CONCRETE OVERLAY (1.50")
1.00	LBS.	REINFORCING STEEL (REPAIR) (GRADE 60) (SET PRICE)
1.00	LBS.	REINFORCING STEEL (REPAIR) (GRADE 60) (EPOXY) (SET PRICE)
1.00	CUYD	MATERIAL FOR PORTLAND CEMENT CONCRETE OVERLAY (SET PRICE)
589.00	SQYD	BRIDGE DECK GROOVING
125.00	SQFT	CONCRETE SURFACE REPAIR
1,078.00	SQYD	MACHINE PREPARATION (0.25")
70.00	SQYD	AREA PREPARED FOR PATCHING
25.00	SQYD	AREA PREPARED FOR PATCHING (FULL DEPTH)
1.00	LBS.	REINFORCING STEEL (REPAIR) (GRADE 60) (SET PRICE)
1.00	LBS.	REINFORCING STEEL (REPAIR) (GRADE 60) (EPOXY) (SET PRICE)
1,078.00	SQYD	MULTI-LAYER POLYMER CONCRETE OVERLAY
1.40	CUYD	CONCRETE (GRADE 4.0) (AE) (SA)
440.00	SQFT	CONCRETE SURFACE REPAIR
130.00	TON	HMA-COMMERCIAL GRADE (CLASS A)
348.00	SQYD	AGGREGATE BASE (AB-3) (6")
42.00	TON	PAVEMENT EDGE WEDGE (ROCK)
1.00	MGAL	WATER (AGGREGATE BASE) (SET PRICE)
1.00	MGAL	WATER (EARTHWORK COMPACTION) (SET PRICE)
2,970.00	EADA	WORK ZONE SIGNS (0 TO 9.25 SQ.FT.)
3,920.00	EADA	WORK ZONE SIGNS (9.26 TO 16.25 SQ.FT.)
1,080.00	EADA	WORK ZONE BARRICADES (TYPE 3 - 4 TO 12 LIN. FT.)
8,640.00	EADA	CHANNELIZER (FIXED)
6,750.00	EADA	CHANNELIZER (PORTABLE)
2,970.00	EADA	WORK ZONE WARNING LIGHT (TYPE "A" LOW INTENSITY)
160.00	STAL	PAVEMENT MARKING (TEMP) 4" SOLID (TYPE I)
5.00	STAL	PAVEMENT MARKING (TEMP) (SOLID) (LINE MASKING TAPE)
2.00	STAL	PAVEMENT MARKING (TEMP) (BROKEN) (LINE MASKING TAPE)
710.00	LNFT	PAVEMENT MARKING REMOVAL
1.00	LS	TRAFFIC CONTROL (INITIAL SETUP)
44.00	EACH	RIGID RAISED PAVEMENT MARKER (TYPE I)
1.00	LS	TRAFFIC SIGNAL INSTALLATION (TEMPORARY)

*** END OF CONTRACT ***

SUMMARY OF QUANTITIES

DATE: 05/19/2023

LETTING DATE: June 21, 2023

TIME: 04:00pm

523066414

STATE PROJECT NO: U169-001 KA 6885-01

DBE GOAL:

WORKING DAYS: 35 COMPLETION DATE:

COUNTY: ALLEN

LIGHTING. US-169: REPLACE HIGH MAST TOWERS AT WAKEENEY REST AREAS (WB/EB) IN AL CO.

QUANTITY	UNIT	ITEM DESCRIPTION
1.00	LS	MOBILIZATION
1.00	LS	CONTRACTOR CONSTRUCTION STAKING
1.00	LS	TRAFFIC CONTROL
30.00	HOUR	FLAGGER (SET PRICE)
1.00	LS	ELECTRIC LIGHTING SYSTEM
1.00	EACH	HIGH MAST LIGHT TOWER (100') (48" CONCRETE BASE)
1.00	EACH	HIGH MAST LIGHT TOWER (110') (48" CONCRETE BASE)
1.00	EACH	HIGH MAST LIGHT TOWER (120') (48" CONCRETE BASE)
*** END OF CONTRACT ***		

KANSAS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES

21

LETTING DATE: June 21, 2023

DATE: 05/19/2023
TIME: 04:00pm

523066424 STATE PROJECT NO: K047-67 KA 6855-01 DBE GOAL:
WORKING DAYS: 40 COMPLETION DATE:
COUNTY: NEOSHO
SIDEWALK IMPROVEMENTS. VAR LOC ON K-47 IN ST. PAUL IN NO CO.

QUANTITY	UNIT	ITEM DESCRIPTION
1.00	LS	MOBILIZATION
1.00	LS	CONTRACTOR CONSTRUCTION STAKING
1.00	LS	TRAFFIC CONTROL
1.00	HOURL	FLAGGER (SET PRICE)
1.00	LS	CLEARING AND GRUBBING
21.00	CUYD	COMMON EXCAVATION (URB)
10.00	CUYD	ROCK EXCAVATION
74.00	SQYD	SIDEWALK CONSTRUCTION (4") (AE)
87.00	SQYD	SIDEWALK RAMP
392.00	SQFT	TEMPORARY PEDESTRIAN SURFACE
10.00	STAL	PAVEMENT MARKING (TEMP) 4" SOLID (TYPE I)
2.00	STAL	PAVEMENT MARKING (TEMP) (SOLID) (LINE MASKING TAPE)
1.00	CUYD	SEDIMENT REMOVAL (SET PRICE)
1.00	LNFT	TEMPORARY BERM (SET PRICE)
112.00	LNFT	FILTER SOCK (8")
1.00	MGAL	WATER (EROSION CONTROL) (SET PRICE)
134.00	LNFT	CURB AND GUTTER, COMBINED (AE)
1.00	LS	SIGN (REMOVE AND RESET)
28.00	LNFT	SIGN POST (4" X 6" WOOD) (FLAT SHEET SIGN)
96.00	LNFT	PAVEMENT MARKING (INTERSECTION GRADE) (WHITE) (24")
1.00	LS	SEEDING

*** END OF CONTRACT ***