

201 - CLEARING AND GRUBBING

SECTION 201

CLEARING AND GRUBBING

201.1 DESCRIPTION

Clear and grub the vegetation and debris as specified in the Contract Documents.

BID ITEM

Clearing and Grubbing

UNITS

Lump Sum

201.2 MATERIALS

Backfill stump holes using granular material or loose friable soil from the project. Use material that is free of excess moisture, frozen lumps, roots, sod, rocks greater than 4 inches in diameter or other deleterious material.

The Engineer will accept the backfill material based on visual inspection.

201.3 CONSTRUCTION REQUIREMENTS

Do not damage any vegetation designated to remain. The Engineer will identify any trees, shrubs and other vegetation designated to remain. Remove low hanging, unsound or unsightly branches on trees and shrubs designated to remain as specified in the Contract Documents. Trim the branches according to recognized industry practices.

Within the construction limits, clear and grub all vegetation not designated to remain. Undisturbed stumps and roots no more than 6 inches above the original ground line or low water level may remain, provided they are a minimum of 3 feet below the finished subgrade or embankment slope and approved by the Engineer.

Remove and dispose of the cleared vegetation and debris. If authorized by the Engineer, dispose of the cleared vegetation and debris on the right-of-way.

Backfill and compact all stump holes, except in areas of excavation. Backfill the stump holes to the level of the surrounding ground. If the backfill area is within the limits of the new construction, compact the backfill to the type of compaction and within the moisture range designated in the Contract Documents.

Provide temporary erosion and pollution control according to **SECTION 901**.

201.4 MEASUREMENT AND PAYMENT

The Engineer will measure the clearing and grubbing as a lump sum.

Payment for "Clearing and Grubbing" at the contract unit price is full compensation for the specified work.