1712 - PRE-FABRICATED VERTICAL DRAIN

SECTION 1712

PRE-FABRICATED VERTICAL DRAIN

1712.1 DESCRIPTION

This specification covers the requirements for prefabricated vertical drains.

1712.2 REQUIREMENTS

Provide a prefabricated polypropylene channeled core wrapped in a non-woven polypropylene continuous filament geotextile complying with the minimum, minimum average roll values in **TABLES 1712-1 and 1712-2**.

TABLE 1712-1: PREFABRICATED VERTICAL DRAIN FABRIC, MINIMUM AVERAGE ROLL VALUES			
Property	Requirement	Test Method	
Grab Tensile Strength	130 lbs	ASTM D4632	
Grab Elongation at Failure	> 50%	ASTM D4632	
Trapezoidal Tear	60 lbs	ASTM D4533	
Permittivity	0.5 sec ⁻¹	ASTM D4491	
Apparent Opening Size (AOS)	≤ 0.3 mm	ASTM D4751	

TABLE 1712-2: PREFABRICATED VERTICAL DRAIN COMPOSITE, MINIMUM AVERAGE ROLL VALUES		
Discharge	Capacity Requirement	Test Method
1.5 gpm	1.5 psi	ASTM D4716
1.5 gpm	43.5 psi	ASTM D4716

1712.3 TEST METHODS

Test in accordance with the requirements stated in **subsection 1712.2**.

1712.4 PREQUALIFICATION

None required.

1712.5 BASIS OF ACCEPTANCE

The Engineer will accept the geosynthetic material upon the basis of satisfactory test results for each lot. A lot is defined as 10,000 feet. If the material fails to comply with the requirements, the entire lot will be rejected.

Any geosynthetic material proposed for use must be evaluated by the Bureau of Structures and Geotechnical Services, Geotechnical Unit, Soils Section. The entire lot of geosynthetic material must be on site before samples are taken and laboratory testing performed.

Allow a minimum of 15 working days for the approval process. After sufficient data has been collected, the testing frequency may be modified upon approval by the Chief Geotechnical Engineer.