

**KANSAS DEPARTMENT OF TRANSPORTATION  
SPECIAL PROVISION TO THE  
STANDARD SPECIFICATIONS, 2015 EDITION**

**SECTION 2211**

**THERMOPLASTIC PAVEMENT MARKING MATERIAL**

**Page 2200-15, subsection 2211.2, add the following:**

**g. Verification Testing.** The Engineer will take verification samples of thermoplastic material from 1 lot of each color per project, using KT-30. Send the samples to MRC for testing and evaluation. Lots previously tested by MRC will be exempt from testing, and may be exempt from sampling if coordinated with MRC.

**Page 2200-15, delete subsection 2211.3a.(4) and replace with the following:**

(4) Titanium Dioxide. KTMR-40, Titanium Dioxide Content in Thermoplastic and Sprayed Thermoplastic Pavement Marking Material.

**SECTION 2212**

**PREFORMED THERMOPLASTIC PAVEMENT MARKING MATERIAL**

**Page 2200-17, subsection 2212.2, add the following:**

**f. Verification Testing.** The Engineer will take verification samples of thermoplastic material from 1 lot of each color per project. Do not sample preformed symbols. Send the samples to MRC for testing and evaluation. Lots previously tested by MRC will be exempt from testing, and may be exempt from sampling if coordinated with MRC.

**SECTION 2213**

**SPRAYED THERMOPLASTIC PAVEMENT MARKING MATERIAL**

**Page 2200-19, subsection 2213.2, add the following:**

**g. Verification Testing.** The Engineer will take verification samples of thermoplastic material from 1 lot of each color per project, using KT-30. Send the samples to MRC for testing and evaluation. Lots previously tested by MRC will be exempt from testing, and may be exempt from sampling if coordinated with MRC.

**Page 2200-20, delete subsection 2213.3a.(4) and replace with the following:**

(4) Titanium Dioxide. KTMR-40, Titanium Dioxide Content in Thermoplastic and Sprayed Thermoplastic Pavement Marking Material.